



**INTERNATIONAL AGENCY FOR RESEARCH ON CANCER
CENTRE INTERNATIONAL DE RECHERCHE SUR LE CANCER**

**Governing Council
Fifty-first Session**

GC/51/10 Corr.1

04/05/2009

*Lyon, 14–15 May 2009
Auditorium*

**REPORT OF THE WORKING GROUP
TO EXAMINE IARC INFRASTRUCTURE PROJECTS
(INCLUDING FINANCIAL ASPECTS)**

CORRIGENDUM

Kindly replace the table "Infrastructure maintenance projects" on page 6 of document GC/51/10 with the table below. The grand total should read 4286 Keuros instead of 3535 Keuros.

Infrastructure maintenance projects

The only objective of this investment plan is to maintain the structure of the building in a good condition and to list the actions that technical necessity requires.
The strategic or development choices presented in the Infrastructure Projects 2008-2017 are therefore not included in our planning.
As a last point, the costs for the renovation of the different floors have been split by components.

	WORK TO BE UNDERTAKEN	Lyon 2010	IARC 2010	Lyon 2011	IARC 2011	Lyon 2012	IARC 2012	Lyon 2013	IARC 2013	Lyon 2014	IARC 2014	Lyon 2015	IARC 2015	Lyon 2016	IARC 2016	Lyon 2017	IARC 2017	TOTAL (Keuros)
Main heating plant	Rehabilitation	172	28	172	28													400
Main heating plant & air-conditioning plant	Heat sources	108	18	108	18													251
Main heating plant & air-conditioning plant	Cost of study by principal contractor	100																100
Roof terrace Tower building	Repairs to weatherproofing			70														70
Roof EPIC	Preventive treatment EPIC		3															3
Façade elements Tower building	Complete overhaul									425		425						850
Technical premises	Filling of cracks	6																6
Floor coverings Tower building	Replacement				31		32		32		32		32	32		32		223
Wall coverings Tower building	Replacement				43		43		43		44		44	44		44		305
Suspended ceilings Tower, EPIC & LATARJET	Replacement				44		44		44		44		44	44		45		309
Electrical switchboards	Renewal of meters		6															6
Main heating plant & air-conditioning plant	Renewal of heating plant meters		10															10
Cooling towers	Replacement					425		425										850
Fancoil heating units EPIC	Replacement		33															33
Air conditioning plant (offices, labs, 12th floor)	Replacement			300		300		260										860
Hot water distribution networks	Replacement as and when required		10															10
TOTAL		386	108	650	164	725	119	685	119	425	120	425	120	120		121		4286

The cost of replacing the main heating plant and the air conditioning plant will have to be confirmed by an appropriate survey.
Weatherproofing works on the façade of the Tower building (to be carried out on 75% of the overall surface of the façade) would reduce its energy needs which is why we have given top priority to the rehabilitation of exterior joinery in this future infrastructure plan.